

Other mitigation measures should be presented to the Director of Public Works/City Engineer in writing if they deviate from the acceptable SWPPP. Removal of any residual material is the responsibility of the contractor.

- S. Concrete Truck Washout Areas** – The contractor shall use BMPs as precautions and/or devices for the protection of wetlands, vernal pools and sensitive open space areas, which may border the project, and to assure compliance with the SWPPP.
- T. Dust Control** – Control dust resulting from the performance of the work, either inside or outside the City's right-of-way. No dust shall leave the project site at any time. Appropriate measures such as watering exposed earth surfaces during clearing, grading, earth moving, other site preparation, and project activities shall be taken throughout the day to minimize dust and provide appropriate air quality. Work shall be curtailed when wind exceeds 15-miles per hour, and at the direction of the Director of Public Works/City Engineer if adequate air quality cannot be maintained.

In addition to meeting the requirements of the Director of Public Works/City Engineer, the project shall be in compliance with the Placer County Air Pollution Control District.

Prior to using any chemical additives for dust control, or for the use of any dust palliative, written approval from the Director of Public Works/City Engineer through the submittal process shall be obtained. The Director of Public Works/City Engineer shall consider only products whose performance has been certified by the California Air Resources Board for approval. (Refer to Section 7 Grading in these Public Facilities Improvement Standards and the Caltrans Standard Specifications Sections 17 and 18 for additional information.)

If non-potable or reclaimed water is used for dust control, copies of applicable permits or waivers from the Regional Water Quality Control Board shall be given to the Director of Public Works/City Engineer and available on-site at all times. All tanks and conveyances shall be properly labeled with warnings and have appropriate cross connection measures in place and used at all times pursuant with the State of California Administrative Code, Title 17—Public Health entitled "Regulations Relating to Cross-Connections".

- U. Working Hours** – Be knowledgeable of the City of Lincoln's noise ordinance that regulates the hours of project construction which shall be limited to:

7:00 AM to 7:00 PM

Monday through Friday

Work between 8:00 AM to 5:00 PM on Saturday, Sunday and Holidays requires a written request to the Director of Public Works/City Engineer 72-hours prior to the desired construction. If work is allowed outside regular work hours, the Contractor shall have a copy of the written approval available at the work site. Work is defined as having equipment engines running, however, workers shall not be on site more than ½-hour before and after work times, and shall be performing work related functions.

Any deviation to the above working hours has special requirements and needs written permission of the Director of Public Works/City Engineer and City Police Chief.

There may be additional limitations placed on working hours specified on the project's approved plans, conditions of approval, special provisions, or encroachment permit.

- V. Cultural Resources** – Stop construction immediately if cultural resources are discovered during excavation operations. It is possible that previous activities have obscured surface evidence of cultural resources. If signs of an archeological site, such as any unusual amounts of stone, bone or shell are uncovered during grading or other construction activities, work shall be immediately halted within 100 feet of the find. The City of Lincoln Community Development Department (CDD) shall be notified immediately. The City CDD shall consult a qualified archaeologist for an on-site evaluation. The City shall collect additional fees based on actual cost incurred for the archeologist. The archaeologist may require additional mitigation.
- W. Hazardous Materials** – Immediately contact the City of Lincoln Fire Department should construction operations uncover hazardous materials, or materials, which the Contractor believes may be hazardous waste, as, defined in Section 25117 of the Health and Safety Code. This material is required to be removed to a Class I, Class II or Class III disposal site in accordance with provisions of existing law. The area containing the hazardous material shall be marked and securely protected until an investigation by a member of the Fire Department is conducted.
- X. Work Zone Traffic Control** – Provide a traffic control plan whenever traffic flow is impacted by the project, or as required by the Police Department or Director of Public Works/City Engineer. The traffic plan shall receive approval from the Police Department and the Director of Public Works/City Engineer prior to being in effect.

In preparation of the Traffic Control Plan, the Contractor is referred to the State of California Standard Plans, or State of California Manual of Traffic